Maintenance Depot Electrification & Track Renewal

Project owner	Infrastructure & Facilities	**Budget (CAPEX)**	€ 9,200,000
Planned start	Q3 2027	**Planned completion**	Q3 2028

1. Project description

Renewal of 11 km of depot track and 34 turnouts, plus electrification of 6 stabling sidings with 15 kV 16.7 Hz overhead contact line. A new pit road with under-floor wheel lathe and a 4-car battery-EMU charging point are added. The depot must remain operational during works; tracks are renewed one by one in 2-week blocks.

2. Objectives

- Allow overnight stabling of battery-electric fleet
- Cut diesel shunting by 90%
- Replace end-of-life 1970s turnouts
- Reduce track maintenance cost by 25%

3. Bill of materials

#	Item ID	Description	Standard	Qty	Supplier ID	Supplier
01	022-001	Rail 60E1, R260, 18 m	EN 13674-1	1,320 t	SUPP_09580	Strategic Systems 525
02	022-002	Concrete sleeper B70 with fastenings	EN 13230	18,400 pc	SUPP_00107	Strategic Group 921
03	022-003	Turnout 60E1-300-1:9, complete	EN 13232	34 set	SUPP_02616	Advanced Industries 425
04	022-004	Elastic rail fastening system	EN 13481	36,800 set	SUPP_06925	Apex Logistics 903
05	022-005	Track ballast 31.5/50, granite	EN 13450	22,000 t	SUPP_05575	Advanced Industries 533
06	022-006	Thermite welding kit	EN 14730	900 kit	SUPP_04553	Strategic Systems 687
07	022-007	Contact wire AC-120 CuAg	EN 50149	14 km	SUPP_02548	Advanced Technologies 166
08	022-008	OCL mast, H-beam, galvanised	EN 50119	210 pc	SUPP_03528	Dynamic Technologies 357
09	022-009	Cantilever assembly, aluminium	EN 50119	210 set	SUPP_05515	Advanced Logistics 120
10	022-010	Section insulator 15 kV	EN 50119	18 pc	SUPP_01675	Global Solutions 619
11	022-011	Under-floor wheel lathe, tandem	EN 13260	1 pc	SUPP_01520	Precision Logistics 169
12	022-012	Battery-EMU charging station 1.5 MW	EN 50388	1 pc	SUPP_06225	Precision Technologies 644

4. Procurement notes

- Suppliers listed are the current preferred source per item; alternatives may be proposed after risk review.
- All items require ISO/TS 22163 (IRIS) or equivalent certification and first article inspection before series delivery.
- Supplier due diligence per LkSG / CSDDD is required before purchase order release.

SIMULATED DEMO DOCUMENT – fictitious project for hackathon use. Supplier IDs and names refer to supplier_risk_dataset.csv.